

Due to late delivery of elastomeric bearings and time pressure to finish with structure concreting work, Contractor install temporary supports to transfer loads from superstructure onto substructure.

Upon arrival of the bearings Freyssinet was assigned to conduct lifting of the structure to allow removal of temporary supports and installation of new bearings.

After approval of Freyssinet design and methodology for lifting work, full activity on site was completed within 3 weeks respecting all project QHSE requirements.

Repairs

Bridge Lifting Work Dubai Parks Hotel Access Bridge Dubai - UAE



Solutions
Foreva

Client

Dubai Parks & Resorts

Consultant

Khatib & Alami

Contractor

Ghantoot Road Contracting

Execution

August 2016

Freyssinet Gulf LLC, PO Box 36211, Dubai, UAE

Tel: +971 4 2094 900 - Fax: +971 4 2094 910

fme@freyssinet.sofr.me www.freyssinet-me.com