

Following successful execution of lifting works on Pedestrian Bridge 1, Freyssinet was assigned to conduct lifting on several locations of Pedestrian Bridge 2 in order to allow Contractor installation and reinstatement of several bearings.

Jacks with capacity 520t and 260t were used depending on lifting location and calculated loads.

The full activity on site was completed during period of 2 weeks respecting all project QSE requirements.

Bridge Lifting Work Pedestrian bridge 2 Dubai Parks & Resorts Dubai - UAE



Client

Dubai Parks & Resorts

Consultant

Consultant HSS

Contractor

Al Nasr Contracting

Execution

July 2016

Freyssinet Gulf LLC, PO Box 36211, Dubai, UAE

Tel: +971 4 2094 900 - Fax: +971 4 2094 910

fme@freyssinet.sofr.me www.freyssinet-me.com